

PROJECT ADDRESS
 Date of submission
 Date of plans
ROUGH CARPENTRY

\$ -

ROUGH CARPENTRY TAKEOFF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST	SUB TOTAL
ROUGH CARPENTRY											
DOORS, FRAMES & HARDWARES											
DOORS & FRAMES											
1											
2	A-101	A-701		Door Type: 2G Size: (2) 3'-0" x 7'-0" x 1-3/4" Door Material: STL Frame Material: STL Note: W/ Glass Panels	2	0%	2	EA.	\$ -	\$ -	
3	A-101	A-701		Door Type: F Size: (2) 3'-0" x 7'-0" x 1-3/4" Door Material: STL Frame Material: STL	1	0%	1	EA.	\$ -	\$ -	
4	A-101	A-701		Door Type: F Size: 3'-0" x 7'-0" x 1-3/4" Door Material: STL Frame Material: STL	8	0%	8	EA.	\$ -	\$ -	
HARDWARE											
HARDWARE SET No. 1											
5											
6											
7	A-101	A-701		Hinge (6 EA.) 5BB1HW 4.5x4.5 652 Ives	12	0%	12	EA.	\$ -	\$ -	
8	A-101	A-701		Panic Device (1 EA.) 25-C-EO 26D Falcon	2	0%	2	EA.	\$ -	\$ -	
9	A-101	A-701		Panic Device (1 EA.) 25-C-L-511L-DANE 32D Falcon	2	0%	2	EA.	\$ -	\$ -	
10	A-101	A-701		Sfic Core (1 EA.) C607 626 Falcon	2	0%	2	EA.	\$ -	\$ -	
11	A-101	A-701		Surface Closer (2 EA.) SC71SS 689 Falcon	4	0%	4	EA.	\$ -	\$ -	
12	A-101	A-701		Seals (1 Set) 8144 Blk Zero	2	0%	2	EA.	\$ -	\$ -	
13	A-101	A-701		Door Weep (2 EA.) 8193AA Al Zero	4	0%	4	EA.	\$ -	\$ -	
14	A-101	A-701		Threshold (1 EA.) 546A Al Zero	2	0%	2	EA.	\$ -	\$ -	

PROJECT ADDRESS
 Date of submission
 Date of plans
ROUGH CARPENTRY

\$ -

ROUGH CARPENTRY TAKEOFF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST	SUB TOTAL
15				HARDWARE SET No. 2							
16	A-101	A-701		Hinge (3 EA.) 5BB1HW 4.5x4.5 652 Ives	12	0%	12	EA.	\$ -	\$ -	
17	A-101	A-701		Office Lock (1 EA.) T521HD7 DANE 626 Falcon	4	0%	4	EA.	\$ -	\$ -	
18	A-101	A-701		Sfic Core (1 EA.) C607 626 Falcon	4	0%	4	EA.	\$ -	\$ -	
19	A-101	A-701		Kick Plate (1 EA.) 8400 8" x 2" LDW 630 Ives	4	0%	4	EA.	\$ -	\$ -	
20	A-101	A-701		Mop Plate (1 EA.) 8400 8" x 1" LDW 630 Ives	4	0%	4	EA.	\$ -	\$ -	
21	A-101	A-701		Wall Stop (1 EA.) WS407CCV 626 Ives	4	0%	4	EA.	\$ -	\$ -	
22	A-101	A-701		Silencer (3 EA.) SR64 Gry Ives	12	0%	12	EA.	\$ -	\$ -	
23				HARDWARE SET No. 3							
24	A-101	A-701		Hinge (3 EA.) 5BB1HW 4.5x4.5 652 Ives	3	0%	3	EA.	\$ -	\$ -	
25	A-101	A-701		Storeroom Lock (1 EA.) T581HD7 DANE 626 Falcon	1	0%	1	EA.	\$ -	\$ -	
26	A-101	A-701		Sfic Core (1 EA.) C607 626 Falcon	1	0%	1	EA.	\$ -	\$ -	
27	A-101	A-701		Kick Plate (1 EA.) 8400 8" x 2" LDW 630 Ives	1	0%	1	EA.	\$ -	\$ -	
28	A-101	A-701		Mop Plate (1 EA.) 8400 8" x 1" LDW 630 Ives	1	0%	1	EA.	\$ -	\$ -	
29	A-101	A-701		Wall Stop (1 EA.) WS407CCV 626 Ives	1	0%	1	EA.	\$ -	\$ -	
30	A-101	A-701		Silencer (3 EA.) SR64 Gry Ives	3	0%	3	EA.	\$ -	\$ -	
31				HARDWARE SET No. 4							

PROJECT ADDRESS
 Date of submission
 Date of plans
ROUGH CARPENTRY

\$ -

ROUGH CARPENTRY TAKEOFF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST	SUB TOTAL
32	A-101	A-701		Hinge (3 EA.) 5BB1HW 4.5x4.5 652 Ives	6	0%	6	EA.	\$ -	\$ -	
33	A-101	A-701		Push Plate (1 EA.) 8200 4" x 16" 630 Ives	2	0%	2	EA.	\$ -	\$ -	
34	A-101	A-701		Pull Plate (1 EA.) 8302 4" x 16" 630 Ives	2	0%	2	EA.	\$ -	\$ -	
35	A-101	A-701		Surface Closer (1 EA.) SC81 RW 689 Falcon	2	0%	2	EA.	\$ -	\$ -	
36	A-101	A-701		Wall Stop (1 EA.) WS407CCV 626 Ives	2	0%	2	EA.	\$ -	\$ -	
37	A-101	A-701		Silencer (3 EA.) SR64 Gry Ives	4	0%	4	EA.	\$ -	\$ -	
38				HARDWARE SET No. 5							
39	A-101	A-701		Hinge (6 EA.) 5BB1HW 4.5x4.5 652 Ives	6	0%	6	EA.	\$ -	\$ -	
40	A-101	A-701		Surface Bolt (2 EA.) SB453-8-TB 604 Ives	2	0%	2	EA.	\$ -	\$ -	
41	A-101	A-701		Storeroom Lock (1 EA.) T581HD7 DANE 626 Falcon	1	0%	1	EA.	\$ -	\$ -	
42	A-101	A-701		Sfic Core (1 EA.) C607 626 Falcon	1	0%	1	EA.	\$ -	\$ -	
43	A-101	A-701		Overhead Holder (2 EA.) 104H 630 Glynn-Johson	2	0%	2	EA.	\$ -	\$ -	
44	A-101	A-701		Kick Plate (2 EA.) 8400 8" x 2" LDW 630 Ives	2	0%	2	EA.	\$ -	\$ -	
45	A-101	A-701		Threshold (1 EA.) 546A Al Zero	1	0%	1	EA.	\$ -	\$ -	
46	A-101	A-701		Silencer (2 EA.) SR64 Gry Ives	2	0%	2	EA.	\$ -	\$ -	
47				HARDWARE SET No. 6							
48	A-101	A-701		Hinge (3 EA.) 5BB1HW 4.5x4.5 652 Ives	3	0%	3	EA.	\$ -	\$ -	

PROJECT ADDRESS
 Date of submission
 Date of plans
ROUGH CARPENTRY

\$ -

ROUGH CARPENTRY TAKEOFF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST	SUB TOTAL
49	A-101	A-701		Storeroom Lock (1 EA.) T581HD7 DANE 626 Falcon	1	0%	1	EA.	\$ -	\$ -	
50	A-101	A-701		Sfic Core (1 EA.) C607 626 Falcon	1	0%	1	EA.	\$ -	\$ -	
51	A-101	A-701		Overhead Holder (1 EA.) 104H 630 Glynn-Johson	1	0%	1	EA.	\$ -	\$ -	
52	A-101	A-701		Kick Plate (1 EA.) 8400 8" x 2" LDW 630 Ives	1	0%	1	EA.	\$ -	\$ -	
53	A-101	A-701		Threshold (1 EA.) 546A Al Zero	1	0%	1	EA.	\$ -	\$ -	
54	A-101	A-701		Silencer (2 EA.) SR64 Gry Ives	2	0%	2	EA.	\$ -	\$ -	
				BATHROOM ACCESSORIES							
				ACCESSORIES							
55	A-101	A-503		Mark: TA-1a Description: Mirror Manuf.: Bradley Corp. Model No.:781-2436 Notes: Channel Frame Mirror	8	0%	8	EA.	\$ -	\$ -	
56	A-101	A-503		Mark: TA-1b Description: Mirror Manuf.: Bradley Corp. Model No.:740-2436 Notes: Fix Tilt Mirror	2	0%	2	EA.	\$ -	\$ -	
57	A-101	A-503		Mark: TA-2a Description: Horizontal Grab Bar (Rear Wall) Manuf.: Bradley Corp. Model No.:8120-00136 Notes: 1 1/2" Grab Bar w/ Concealed Mounting	2	0%	2	EA.	\$ -	\$ -	
58	A-101	A-503		Mark: TA-2b Description: Horizontal Grab Bar (Side Wall) Manuf.: Bradley Corp. Model No.:8120-00142 Notes: 1 1/2" Grab Bar w/ Concealed Mounting	2	0%	2	EA.	\$ -	\$ -	

PROJECT ADDRESS
 Date of submission
 Date of plans
ROUGH CARPENTRY

\$ -

ROUGH CARPENTRY TAKEOFF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST	SUB TOTAL
59	A-101	A-503		Mark: TA-2c Description: Horizontal Grab Bar (Side Wall) Manuf.: Bradley Corp. Model No.:8120-00118 Notes: 1 1/2" Grab Bar w/ Concealed Mounting	2	0%	2	EA.	\$ -	\$ -	
60	A-101	A-503		Mark: TA-3 Description: Toilet Tissue Holder Manuf.: Bradley Corp. Model No.: 5402 Notes: Surface Mounted	8	0%	8	EA.	\$ -	\$ -	
61	A-101	A-503		Mark: TA-4 Description: Towel Dispenser / Waste Receptacle Manuf.: Bradley Corp. Model No.: 235-11 Notes: Surface Mounted	4	0%	4	EA.	\$ -	\$ -	
62	A-101	A-503		Mark: TA-5 Description: Soap Dispenser Manuf.: Bradley Corp. Model No.: 6562 Notes: Surface Mounted	8	0%	8	EA.	\$ -	\$ -	
63	A-101	A-503		Mark: TA-6 Description: Napkin Receptacle Manuf.: Bradley Corp. Model No.: 4A10-11 Notes: Surface Mounted	5	0%	5	EA.	\$ -	\$ -	
64	A-101	A-503		Mark: TA-7 Description: Baby Changing Station Manuf.: Bradley Corp. Model No.: 9631 Notes: Surface Mounted	2	0%	2	EA.	\$ -	\$ -	
65	A-101	A-503		Mark: TA-8 Description: Hook and Bumper Manuf.: Bradley Corp. Model No.: 915 Notes: Surface Mounted	16	0%	16	EA.	\$ -	\$ -	

PROJECT ADDRESS
 Date of submission
 Date of plans
 ROUGH CARPENTRY \$ -

ROUGH CARPENTRY TAKEOFF



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	UNIT COST	TOTAL COST	SUB TOTAL	
66	A-101			Exterior Free Standing Shower <i>Note: Please Confirm Inclusion In Scope. If included, than add price.</i>	16	0%	16	EA.	\$ -	\$ -		
67	A-101	A-503		Toilet Partition	135	10%	149	LF	\$ -	\$ -		
68	A-101	A-503		Urinal Partition	3	10%	3	LF	\$ -	\$ -		
FIRE EXTINGUISHERS												
69	A-101			Fire Extinguishers	2	0%	2	EA.	\$ -	\$ -		
BLOCKING												
70	A-101			2x Blocking for Toilet Accessories	292	10%	321	LF	\$ -	\$ -		
71	A-101			2x8 PT Blocking for Other Items	34	10%	37	LF	\$ -	\$ -		
SUB TOTAL											\$ -	
SUB TOTAL										\$ -	\$ -	
O&P										20%	\$ -	\$ -
ROUGH CARPENTRY										\$ -	\$ -	